

INTERNATIONAL INDIAN SCHOOL - JEDDAH

UNDER THE PATRONAGE OF EMBASSY OF INDIA, RIYADH
AND AFFILIATED TO CENTRAL BOARD OF SECONDARY EDUCATION, NEW DELHI - INDIA
MEMBER, COUNCIL OF C.B.S.E. SCHOOL IN GULF
AFFILIATION NO. 5730001, SCHOOL CODE - 90072
MINISTRY OF EDUCATION - K.S.A - LICENCE NO. 045 / J, C.C.No. 136593
P.O. Box 14861 JEDDAH 21434, SAUDI ARABIA
Boys' Section - Tel. +966 12 6751536 / 6711934 / 6712097
Girls' Section - Tel. +966 12 6721607 / 6718345
Girls' Section I & II - Tel. +966 12 6737752, KG-SECTION - Tel. +966 12 6747737



المدرسة الهندية العالمية - جدة

تحت رعاية سفارة الهند، الرياض
وتابعة للمجلس المركزي للتعليم الثانوي، نيودلهي - الهند
عضو مجلس C.B.S.E. مدرسة في الخليج
الانتماء رقم. ٥٧٣٠٠٠١ رمز المدرسة - ٩٠٠٧٢
وزارة التعليم - ترخيص رقم - ج/٠٤٥ رقم العضوية: ١٣٦٥٩٣
ص.ب: ١٤٨٦١ جدة ٢١٤٣٤، المملكة العربية السعودية
ت: قسم البنين: +٩٦٦ ١٢ ٦٧٥١٥٣٦ / +٩٦٦ ١٢ ٦٧١٩٣٤ / ٦٧١٢٠٩٧
ت: قسم البنات: +٩٦٦ ١٢ ٦٧٢١٦٠٧ / ٦٧١٨٣٤٥
ت: قسم البنات للصف الأول والثاني: +٩٦٦ ١٢ ٦٧٣٧٥٢، روضة وتمهيدي - +٩٦٦ ١٢ ٦٧٤٧٧٣٧

TENDER NOTICE

(For Fire Fighting Installation)

Ref: IISJ/Fire Fighting Installation GS/ADM/2023

Date: May 7, 2023

Sealed Quotations are invited from the Civil Defense approved firm/company for installation of Fire Fighting Equipments at Girls' Section Building of International Indian School, Jeddah. The complete Fire Fighting design package (BOQ) is attached with this notice.

The last date of submission of quotation separately (Technical & Financial) is May 22, 2023. The Bids may also be submitted on tenders@iisjed.org within the stipulated date.

Administrative Officer

Principal



Firefighting

		Qty	Unit	Unit Rate	Amount
Supply, install, testing, commissioning and put into operation fire fighting system which include the following :					
1	Operate the Fire Pump items as specified and shown on the drawings, equipment schedule and specifications. System shall include alarm check valve, retard chamber, alarm gong, valves, strainers, vibration isolators, pressure, flexible connections, sensors, electrical connections, bronze-fitted, single stage, double suction, split case centrifugal pump with individual priming pipe connection for each pump suction line with bronze shaft sleeve; case wearing rings and packed stuffing boxes with lantern ring; pump; driver; and other accessories /components as required for a complete and functional installation. The fire Pumps shall be 1 electrical-driven pump with 1 diesel driven pump with 1 jockey pump with diesel engine, diesel storage day tank and accessories. The trim shall be complete with the alarm check valve supervisory switches and connectivity to fire alarm panel. The pump set shall be supplied complete assembled with controller, control panel, all electrical conduits, cables, race ways from pumps to safety switches including testing commissioning and balancing as per specification and standards .	1	kit	1	
2	Recessed type fire hose cabinet complete with 1" angle valve, 30 m long 1" synthetic automatic swinging fire hose reel and 6 kg dry powder fire extinguisher . The door and architrave of the fire hose cabinet shall be stainless steel 316 L, finish to architects approval, back box with mild steel. A sample must be submitted for approval before installation, all parts are according to NFPA-14, drawings and civil defense specifications	14	Pcs		
3	4" x 2.5" x2.5" Siamese connections chromium plated complete including os&y gate valve 4" adapters, plugs, check valve, chains, double clapper, caps, hydrant control valve complying with fire brigade requirements, ..etc. all other accessories as specified and as shown on drawings.	1	Pcs		
4	6kg Powder Fire Extinguisher	50	Pcs		
5	6kg Co2 Fire Extinguisher	5	Pcs		
6	Emergency Light	67	Pcs		
7	Exit light	19	Pcs		
8	2-hours Fire Rated Doors	18	Pcs		

FIRE ALARM SYSTEM and Life safety

		Qty	Unit	Unit Rate	Amount
Supply, install, testing, commissioning and put into operation Addressable Fire Alarm system complete with necessary fire resistant cable, EMT conduit, with all necessary accessories to finish works as per specification and drawing including the following:					
1	Main Fire Alarm Control Panel 16 Zones	1	pcs.		
2	Smoke Detector	209	pcs.		
3	HEAT Detector	0	pcs.		
4	Fire Alarm Manual Call Point	24	pcs.		
5	Fire Alarm Strobe And Horn	24	pcs.		
6	Emergency Exit light	67	Pcs		
7	Emergency exit sign	19	Pcs		
8	2 hours fire rated door	18	Pcs		

should use fire rated wires - EMT

Also	Civil defense remarks that you provided to us	Qty	Unit	Unit Rate	Amount
1	Remove the wooden partition in the northern side and make it with fire rated				
2	Removing the room with a rebound made of non fire rated materials				
3	Opening the end of the emergency ladder leading to the surface				
4	Replacing rack fire hoses with rubber hoses				
5	Remove the grills from the windows				

The BOQ includes all requirements, but what is already on the site and working must be deducted