



INTERNATIONAL INDIAN SCHOOL JEDDAH
SAUDI ARABIA

www.iisjed.org

E-Tender No.: REF/IISJ/EST/ARTIFICIAL GRASS /KG & I-II GS

Date of Publishing : 11/08/ 2026

Last date for submission of bids: 18/08/26 2026

International Indian School, Jeddah

P.O. Box: 14861,

Jeddah - 21434

Kingdom of Saudi Arabia.



TENDER NOTICE

DATE-11/08/2026

Request for Quotation for artificial grass work at KG & I-II GS Building

Contractors/firms having valid license for undertaking landscaping & Civil Engineering work in KG & I-II GS Building of IIS Jeddah.

Interested Parties may quote for the work in accordance with the requirement decided by the School. Please submit your quotation as in the prescribed format hereto

(ANNEXURE-A). Please provide Financial and Technical proposal separately.

The quotation may be submitted through tenders@iisjed.org up to 18/08/2026.

TERMS & CONDITIONS

1. Work shall be carried out as per the instructions of the school authorities.
2. Poor workmanship is liable to be rejected in total.
3. Company Registration, Previous projects, Staff qualification, the list of Equipment own by the company & Client references etc.
4. All Repairs and patch works shall be neatly carried out to match the original finish at contractor's own cost and to the entire satisfaction of the school authorities.
5. All the debris due to maintenance works shall be cleared and site shall be kept clean by the contractor at all the times.
6. The workers engaged for the work shall be qualified, well experienced to carry out the works.
7. In case of any accident during the operation/Maintenance of the equipment leading to injuries/damages to human beings/Equipment's and or loss of life, contractor shall be fully responsible for settling all the claims and indemnity. The School will not take any responsibility against any claims arising out of such accidents.
8. The contractor should possess the valid license for civil and maintenance work undertaking the said job works. Copy of valid CR, VAT registration and company profile should be attached with the quotation.
9. Rates must include all transportation, VAT and other taxes as applicable.
10. Quotations without date, signature, and seal of the firm will be summarily rejected
11. The quotation should be submitted for the required work as per ANNEXURE-A and submitted in the format as per ANNEXURE-B
12. Quantities given in the scope of work (ANNEXURE-A)
13. Lack of any above mentioned documents will be consider as incomplete documents will be rejected.
14. **Quotation should be attested by chamber of commerce.**
15. **Kindly attached previous experience that is relevant to the scope of the tendered work**
16. **Kindly mentioned specification of grass and picture**
17. Note: -Contractor may inspect the site between 10:00 am to 2:00 pm between 12/08/2026 to 18/08/2026



ANNEXURE 'A'

Scope of Work

Supply, Installation, and Commissioning of Artificial Grass

The Contractor shall be responsible for the complete supply, installation, testing, and commissioning of artificial grass for the designated playground with the following dimensions:

- **Length:** 24.08 m
- **Width:** 28.72 m
- **Total Area:** 691.57 m²

The scope of work shall include following:

1. Site Preparation

- Remove all debris, unsuitable materials.
- Carry out leveling, grading, and compaction of the existing ground to provide a stable, uniform, and well-prepared base for the artificial grass installation.

2. Supply of Artificial Grass

- Supply high-quality artificial grass that is UV-resistant, fire-resistant, non-toxic, child-safe, and specifically designed for outdoor playground.
- The artificial grass shall be durable, weather-resistant, and suitable for heavy pedestrian use.

3. Base Materials and Accessories

- Supply and install all required base materials, geotextile (if required), joint tapes, adhesives, fixing pins, edging materials, infill materials (if applicable), and all other accessories necessary to complete the installation.

4. Installation

- Ensure accurate alignment, secure and concealed joints, proper fixing, and adequate drainage to prevent water accumulation.

5. Finishing Works

- Trim and neatly finish the artificial grass around playground edges, boundaries, existing structures, equipment, and fixtures to achieve a clean, safe, and professional appearance.

6. Cleaning and Waste Removal

- Clean the entire work area upon completion.
- Remove and legally dispose of all surplus materials, debris, packaging, and waste generated during the works.

7. Inspection, Testing, and Handover

- Conduct a final inspection to verify that the installation complies with the project specifications and quality standards.
- Perform all necessary testing to ensure the artificial grass system is securely installed, safe for use, and functioning as intended.
- Hand over the completed playground in a clean, safe, and fully operational condition, together with the manufacturer's warranties, maintenance instructions, and all relevant documentation.



ANNEXURE 'B'

Financial BOQ (Bill of quantity) format for the canopy work. Unit rates and amount can be filled by contractor

S.no	Item description	Unit	Quantity	Unit rate (SAR)	Amount
1	Supply and installation of artificial grass-Fire resistant	m ²	691.57		

Total bid amount

Vat 15%

Grand total bid amount

General Requirements: -

- All materials shall be new, of approved quality, Fire resistant and compliant with the project specifications.
- Installation shall be carried out in accordance with good engineering practice and applicable safety regulations.
- Any damage to existing structures during the execution of the works shall be repaired by the contractor at no additional cost.
- Upon completion, the contractor shall clean the work area and hand over the completed works in good condition.



CONTACT DETAILS FORM

Name of the Bidding Firm	
Name of the owner(s) & Nationality	
Name of the Authorized Signatory	
Nationality	
E-Mail ID	
Telephone No. & Mobile No	
Registration(CR) No.	
Service tax (VAT Certificate) no.	
Registered Office & Address (National Address)	
Bank Details (IBAN):	

